ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Abstract Notification, dated 3rd December 1929.

Attention of the public is invited to notice calling for sealed tenders for constructing dry stone revetment to the storm water drain in Kitchatty Chattram road from Central College Hospital compound to road by the side of Mr. C. V. Narasimha Iyengar's house, published on pages 1417 and 1418 of part VI of the *Mysore Gazette*, dated 5th December 1929.

Last date for receiving tenders is 16th December 1929.

Abstract Notification.

Attention of the public is invited to notice calling for sealed tenders for Restoration of Jinnagera Minor Tank Registered No. 54 of Hoskote Taluk, published on pages 1458-1459, Part VI of the *Mysore Gazette*, dated 12th December 1929. The last date for receiving is 30th December 1929.

H. R. VENKATASUBBA RAO,
Executive Engineer.

SANITARY AND TOWN PLANNING DIVISION.

Abstract Notification.

The Attention of the public is invited to tne detailed notification calling for sealed tenders for laying the 9" main in connection with improving the Water Supply to Kolar Town published in pages 1444 of Part VI of the *Mysore Gazette*, dated 12th December 1929.

The last date for receiving tenders is 2nd January 1930.

V. V. PATANKAR,
Executive Engineer.

KOLAR DIVISION.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 1401 and 1402, calling for tenders for Restoring Kempasandra Cholaganahalli Jodi Tank of Malur Taluk.

The latest date for tender is 21st December 1929.

Notice.

The attention of the public is invited to the notification published in the *Mysore Gazette*, Part VI, pages 1402 and 1404, calling for tenders for Restoring Yeldur Santhammanakere Register No. 53—274, Srinivaspur Taluk.

The latest date for tender is 21st December 1929.

Dated 10th December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 22nd January 1929, for Restoring Egvabandlacheruvu Polakalamallayanakere, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3(*a*) Tenders not given on printed forms will be rejected.

4. Each tender must be accompanied by a deposit of rupees one hundred and eighty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Egvabandalacheruvu Polakalamallayanakere," Bagepalli Taluk, in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason what ever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage of or lower than the estimate will not be accepted.

Abstract estimate of quantities of work to be done for Restoring Egvabandalacheruvu Polakalamallayanakere, Register No. 654, Bagepalli Taluk.

Sl. No.	Items of work	Per	Approximate quantity
	Bund R. L. 55·00		
1	Earthwork to bund watering and tamping complete ...	C.yd.	14,258
2	Turfing	S.yd.	3[illegible]018
3	New stone work	C.yd.	[illegible]42
4	Removing and resetting old stone work	,,	51[illegible]
5	Fixing grade stones with numbering and painting complete.	No.	10
6	Fixing index stone do do ...	,,	10
7	Fixing B. M. stones do do ...	,,	2
8	Fixing Register No. stone do do ...	,,	1
9	Fixing gauge stone do do ...	,,	1
10	Gravel backing	C.yd.	612
11	Cutting trees and jungle and removing roots on bund ...	Lump	sum
	Sluice.		
1	Cut opening the bund and examining the tunnel and refilling same after attending to necessary repairs.	Lump	sum
	Waste Weir.		
1	Benching rock 6″ deep 1½′ breadth for the foundation of body wall with the return.	S.ft.	60
2	Burnt brick in surki mortar	C.ft.	123
3	Surki mortar plastering	Sqr.	2·85
4	Burnt stone slabs	S.ft.	59

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification, dated 2nd December 1929.

Attention of the public is drawn to notification calling for tenders for maintenance of Amurthur Doddakere Register No. 64—156, Kunigal Taluk published in Part VI of page 1414 of *Mysore Gazette*, dated 5th December 1929.

The tenders will be received by the Executive Engineer, Tumkur Division till 2 P.M. of 28th December 1929. Earnest money to accompany the tender is Rs. 230.

V. V. PATANKAR,
Executive Engineer.

MYSORE DIVISION.

Abstract Notification, dated 4th December 1929.

"Reference is invited in detail in the *Mysore Gazette*, dated 12th December 1929, on page 1441-1442, intimating the last date of tender for Restoring Mellahally Tank. Reg. No 114 of Nagamangala Taluk.

Dated 6th December 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 3 P.M., on 8th January 1930, for Restoring Theganhalli Minor Tank Reg. No. 16 of Krishnarajpete Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form

4. Each tender must be accompanied by a deposit of Rs. 200 (two hundred only) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for Restoring Theganhalli Minor Tank Reg. No. 16 of Krishnarajpete Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

Abstract estimate for Restoring Theganhalli Minor Tank Reg. No. 16 of Krishnarajpete Taluk.

Sl. No.	Items of work	Per	Quantity
	Bund.		
1	Jungle clearings	Lump	sum
2	Cutting grips to receive new earth	Grade	16
3	Earth work to bund with watering and tamping ...	Cyd.	1830
4	Do to be used to rear slope got from foundation of breach.	,,	191
5	New stone revetment with fresh jelly	,,	344
6	Providing and fixing new grade stones	No.	1
7	Chiseling and painting old and new grade stones ...	,,	17
	(a) Painting index stones	,,	18
8	Providing and fixing Reg. No. and date stone ...	,,	1
9	Do B. M. do	,,	2
10	Do guage	,,	1
11	Turfing the front and rear slopes	Sqr.	363·48
	Breach.		
1	Earthwork excavation including silt clearance	C.yd.	191
2	Do to breach with watering and tamping ...	,,	1,330
3	Puddle wall	,,	274
4	New stone revetment work	,,	126
5	Gravel backing to revetment	,,	60
6	Turfing to front and rear slops	Sqr.	40·50
7	Bailing water	Lump	sum
8	Cutting grips	Do	
	Sluice.		
1	Burnt brick in surki mortar	C.ft.	20
2	Plastering with surki mortar	Sqr.	1·00
3	Pointing and grouting crevices	Lump	sum
4	Providing plug and rod with locking arrangements ...	Do	
5	Sundry repairs if any	Do	
	Left Weir.		
1	Earthwork excavation and using the same to right wing ...	C.yds.	664
2	Surki concrete for foundation	C.ft.	217
3	Burnt brick in surki mortar	,,	374
4	Burnt stone slabs 6" thick	S.ft.	386
5	Plastering with surki mortar	Sqr.	2·00
6	Joggle joints at 6' apart	No.	20
7	New stone work	C.yd.	122
8	Old stone work	,,	67

N. G KRISHNA IYENGAR,
Executive Engineer.